



DFW1500 or approved equal required.

* see below

Note: 6" of clearance on the back side, and 12" of clearance on the control valve side from device center-point is required. Brass caps to be installed in test ports in all underground installations
4" of washed gravel to be installed in bottom of meter box

Any exemptions must be approved by the Public Works Director

*Larger devices will require larger boxes to meet clearance specifications.



City of Red Oak
Public Works
Department

$\frac{1}{2}$ " , $\frac{3}{4}$ " , 1" , 1 $\frac{1}{2}$ " , & 2" Double Check Valve Backflow
Prevention Assembly Installation

Public Works Department
411 W Red Oak Road
Building D
972-576-3414